

DUE DILIGENCE MEMORANDUM

TO: Massachusetts Housing Partnership
Attn: Laura F. Shufelt, Director of Community Assistance
160 Federal Street
Boston, MA 02110

FROM: Zachary Richards, PE
Angela Botto

Date: December 19, 2023

RE: Due Diligence Memorandum
100 Beal Street
Hingham, MA

1.0 INTRODUCTION

This memorandum summarizes due diligence findings and potential site constraints for the subject property identified as 100 Beal Street in Hingham for a proposed affordable housing development. This summary is based on an on-site investigation during November of 2023, property information available at the Town of Hingham, a wetland investigation and delineation conducted by Lucas Environmental, LLC (LE) during November of 2023, Geographic Information System (GIS), and online soil mapping information available at the time of this report.

Massachusetts Housing Partnership (MHP), in conjunction with the Hingham Housing Authority, is reviewing the feasibility of a proposed development located at 100 Beal Street in Hingham, MA (the "Site"). The Site is identified on the Town's assessor database as one parcel, located on Map 58, Block 0, Lot 23 and consists of approximately 15 acres. Based on our current understanding, the project would include the construction of a 30–50-unit, multi-family housing complex, consisting of 1-3 bedroom units (the "Project"). As part of this review, the developable area on site has been identified and is included as **Attachment A**, Development Area Exhibit. Based on a preliminary review of available utility information, existing utility infrastructure within Beal Street includes sewer, water, gas, and overhead electric and telecommunications services to serve the project.

2.0 SITE OVERVIEW

2.1 Existing Conditions

The Site consists of one parcel identified as Map 58, Block 0, Lot 23 in the Town of Hingham. The property is approximately 15.01 acres, and the property boundary is depicted in **Attachment B** which shows the aerial map of the property and the surrounding parcels. Additionally, **Attachment C**, shows the USGS topographical map of Hingham. The Site is bound by Beal Street to the north, Residence E zoned properties to the west, and Official & Open space zoned properties to the south and east. The site has frontage on Beal Street.

The Site is partially developed and contains a residential facility with Bay State Community Services. The facility has an existing driveway and utility connections, and accompanying parking lot in the northwest corner of the lot. It is assumed that the existing building and associated site features to remain as existing. The south west portion of the site is mostly vegetated with bordering wetlands, isolated wetlands a perennial stream, several dilapidated paved areas and access drives. Topography maps shows that site drains from high points in the center of the Site, to wetlands on the north, east and south of the Site. The elevation in Beal Street is generally 4-6 feet higher than the developable area, with localized mounds throughout. A LiDAR exhibit with approximate site topography has been included as **Attachment D** for reference.

The Natural Resource Conservation Service's (NRCS) Web Soil Survey has confirmed soil mapped as 110B - Canton-Chatfield-Rock outcrop complex, very stony, 262E - Quonset sandy loam, 52A - Freetown muck, and 659B - udorthents, gravelly. As the site and building design progresses, it is recommended soil testing be conducted to determine the soil properties in support of foundation and stormwater. The NRCS Web Soil Survey Reports have been included as **Attachment E** for reference.

2.2 Site Access

There is an existing driveway off Beal Street, providing access to the existing facility and parking lot area leading to the developable area identified for this affordable housing project. This existing driveway appears to be the only feasible access to the contemplated area for development due to wetland constraints, site frontage and the location of the existing facility. The driveway configuration should be further evaluated as design advances to ensure suitability for truck and emergency access.

3.0 ZONING

It is our understanding that the project may proceed under Massachusetts General Law Chapter 40B (M.G.L. c.40B), which would provide zoning relief. The Chapter 40B state statute was developed to enable local Zoning Boards of Appeal to approve affordable housing developments under flexible rules if at least 20-25% of the units are set to have long-term affordability restrictions. However, we have provided a zoning analysis herein to give context of typical dimensional requirements for a project in this zoning district currently.

Based on the Town of Hingham Zoning Map, dated April 2015, the site is zoned as Official and Open Space (OO). Per the Town of Hingham Zoning By-law, revised through April 25, 2023, the OO district does not allow multi-family dwellings by-right or through a special permit. See **Attachment F** for additional use regulations.

Table 1, below, outlines specific dimensional requirements in the OO District. See **Attachment F** for additional intensity of use regulations.

Table 1: Dimensional Requirements	
	Official & Open Space (OO)
Minimum Lot Area (sf)	None
Minimum Lot Frontage (ft)	20
Maximum Height (ft)	35
Minimum Lot Coverage (%)	10 (Building)*
Minimum Front Yard (ft)	40
Minimum Side Yard (ft)	40
Maximum Rear Yard (ft)	40
Parking spaces per dwelling units (space/unit)	2 [^]

**A minimum of 15% of the lot shall not be built upon, paved, or parked on. This area shall be maintained either in its natural state or landscaped. A 15' natural green strip is required along street frontage and can be included in this 15% area.*

[^]1.25 space/unit for Elderly Residential. 1 space/unit for Congregate or Assisted Living Facility.

It appears that the proposed addition of multi-family units to the existing Site will comply with the Site's minimum lot area, building height, frontage, front, side and rear setbacks in their current Zoning. It is anticipated that it will not comply with the OO district's use requirements, and will require rezoning, if the Chapter 40.B path is not pursued.

4.0 RESOURCE AREAS

4.1 Resource Area Evaluation

Massachusetts Department of Environmental Protection (MassDEP) Wetlands

Based on publicly available Geographic Information System (GIS) mapping from MassDEP, there are several portions of wetlands and riverfront area located on the site.

Lucas Environmental has flagged, evaluated and provided a detailed summary of the observed wetlands, included as **Attachment G**. The Town of Hingham has a 100-foot buffer, 50-foot no touch buffer along with the State of Massachusetts 100-foot buffer zone to wetland and riverfront area, requiring a Notice of Intent Application. The Commission may at its discretion allowed a proposed structure on a wall-type foundation, landscaping and driveways withing 100 to 50 feet of the Resource Area if sufficient mitigation is provided. No provided mitigation is sufficient to allow landscaping, driveways or a structure less than 50-feet from a Resource Area. The majority of identified wetlands are located towards the south and west property lines of the site. However, Wetland E is a very small wetland area, likely an isolated wetland, located near the existing parking lot, near the center of the Site. This area was previously delineated by others, and while it contains hydric soils, it is essentially devoid of vegetation and lacks hydrological indicators. It is arguably not a wetland resource area. Due to the location of the wetlands, it is anticipated a Notice of Intent will be required for the Project.

Federal Emergency Management Agency (FEMA) 100-Year Flood

The 100-year flood plain does not extend into the Site. Per the FEMA Community Maps, #250268, which was exported on November 10, 2023 there are no based flood elevations on site; therefore, riverine flooding is not anticipated to be a hinderance to a proposed development. A copy of these map is included in **Attachment H**.

MassWildlife's Natural Heritage & Endangered Species Program (NHESP) Certified Vernal Pools

Vernal pools are small bodies of water that provide habitat for distinctive plants and animals. Certified vernal pools are protected if they fall under the jurisdiction of the Massachusetts Wetlands Protection Act. Using publicly available Geographic Information System (GIS) mapping from MassDEP, there is a vernal pool present within the wetlands in southern section of the site. **Attachment G** is resource area exhibit showing the approximate location of the existing vernal pool and its associated 100' buffer area. The vernal pool is located well beyond the developable area and is not anticipated to impact the Project.

Secretary of Energy and Environmental Affairs (EEA) Areas of Critical Environmental Concern

Areas of Critical Environmental Concern (ACECs) are places in Massachusetts that receive special recognition because of the quality, uniqueness and significance of their natural and cultural resources. ACECs are general nominated at community level and are reviewed and designated by the state's EEA Secretary. **Attachment G** shows the extents of ACECs present along the southern section of the site. The presence of the ACEC generally requires stricter environmental review when it comes to new developments, and will need to be considered in the stormwater design and Notice of Intent.

5.0 UTILITY INFRASTRUCTURE

5.1 Sewer Service

5.1.1 Existing Sewer Service

The Hingham Sewer Commission, operates, and maintains the sewer systems within the vicinity of the Project Site, on Beal Street. There is an 8" PVC main within Beal Street along the project limits per record plans on file with the Town of Hingham Department of Public Works. See **Attachment I** for further details of the sewer infrastructure.

5.1.2 Proposed Sewer Connection

Based on the size of the main and the contemplated Project, it is anticipated that the existing sewer main would have capacity to serve the Project. It is recommended that the existing sewer main capacity be further reviewed with the Town as the Project advances. Due to the lower elevation across portions of the Site, as it relates to Beal Street, it is anticipated that a sewer pump station may be required to serve the Project. The sewer pump station would receive flows from the Project and pump discharge uphill to a sewer manhole adjacent to Beal Street where it could then flow by gravity via an 8" sewer service to the existing sewer main in the right-of-way. The proponent will need to provide sewer flow calculations based on the final unit count and coordinate with the Hingham Department of Public Works (DPW) and Hingham Sewer Commission to ensure the proposed system meets their standards and requirements.

5.2 Water Service

5.2.1 Existing Water Service

The Town of Hingham currently owns, operates, and maintains water distribution systems in the vicinity of the Project Site from the Weir River Reservoir. There is currently a 12" water main within the project limits of Beal Street per record plans on file at the Town of Hingham Department of Public Works. See **Attachment I** for further details of the water infrastructure.

5.2.2 Proposed Water Service

Bohler anticipates that the existing water main would have sufficient capacity to serve the Project. It is anticipated that the contemplated project will require a new water main extending from Beal Street, up the proposed access drive, approximately 700' to serve the proposed use. The proponent will need to provide both fire and domestic lines to the proposed development along with hydrants and valves along firetruck routes. Domestic and fire flow calculations based on the final unit count are to be provided and coordinate with the Hingham Department of Public Works (DPW), Weir River Water System, and Hingham Fire Department to ensure the proposed system meets their standards and requirements.

5.3 Storm Drainage System

5.3.1 Existing Storm Drainage System

There are storm drainage pipe systems within Beal Street, owned and operated by the Town of Hingham. There are currently several stormwater structures or BMP's located along the Beal Street R.O.W. These structures include catch basins which capture runoff from the roadway and convey it to the surrounding wetlands via a network of varying pipes (12" CMP, 12" HDPE, 12" RCP), and a headwall. The majority of the Site itself appears to drain to the wetland areas located to the south.

5.2.2 Proposed Storm Drainage System

The proposed development will result in increased impervious area and will require a stormwater management system to retain and infiltrate the additional stormwater runoff. The final size and scope of the stormwater management system will be dependent upon the final concept layout and amount of impervious area, and existing drainage patterns. The proposed stormwater management system will also need to be designed to comply with the Town of Hingham's requirements and standards. It is anticipated that required stormwater system will be provided on site via underground detention or infiltration system that will ultimately overflow to the existing wetlands.

5.4 Electrical Services

Within the vicinity of the Project, Hingham Municipal Lighting Plant is the electrical service provider. Based on the initial site observations and the Site survey there are existing utility poles with overhead electrical lines running along Beal Street. An updated survey is required to determine the existence of utility easements within the site vicinity. The development will need to be reviewed with the Hingham Municipal Lighting Plant to confirm that available services are adequate, or if any required infrastructure and related cost will be required to serve the project, and design requirements in relation to the possible easements present onsite. It is anticipated that the proposed development will need to be served by approximately 700± feet of utility poles and overhead wires or underground conduit, along the length of the access drive to serve the project.

5.5 Telecommunication Services

Within the vicinity of the Project, Xfinity, Verizon, T-Mobile, HughesNet and ViaSat are the telecommunication service providers. Based on the initial site observations there are existing utility poles with overhead telecommunication lines running along Beal Street. The proposed development will need to be reviewed with the private utility providers to confirm that available services are adequate, or if any required infrastructure and related cost will be required to serve the project. It is anticipated that the proposed development will need to be served by approximately 700± feet of utility poles and overhead wires or underground conduit, along the length of the access drive to serve the project.

5.6 Gas Services

Within the vicinity of the Project, National Grid is the gas service provider. It is anticipated that gas service can be extended from the existing gas main in Beal Street to serve the project needs. The development will require review with the private utility provider to confirm that available services and pressure are adequate, or if any required infrastructure and related cost will be required to serve the project. Should gas service be needed for this project, it is anticipated that the proposed development will need to be served by approximately 700± feet of underground gas lines, along the access drive.

6.0 Conclusion

The due diligence for the Site has identified appropriate site access, zoning restrictions, topography, and on-site wetlands to be the biggest challenges for development. The area of development would require an access drive adjacent to the existing building on-site with associated utility mains for water, electric, and gas (if required) extending from Beal Street. The existing curb cut may require redesign to ensure it can properly serve required truck and emergency vehicle access. Additionally, a majority of the Site appears to set at a lower elevation than Beal Street, which may result in the need for a sewer pump station in order to discharge effluent to the gravity sewer main in the right-of-way. Should Chapter 40B zoning relief, or rezoning of the parcels not be pursued, the use of the site per Hingham Zoning By-Laws would not allow the contemplated development. The bordering vegetated wetlands, isolated wetlands and perennial stream appears to be the biggest constraint for this development and constrain the developable area on the Site. It is recommended Wetland E be further evaluated before design progresses. Despite Wetland E, there is adequate area for the proposed housing development, but it is anticipated a Notice of Intent application would be required. Despite the site constraints, the contemplated Project would complement the surrounding housing developments and the Site provides opportunity for an attractive and secluded development with many adjacent walking trails.


ATTACHMENTS

Attachment A – Development Area Exhibit
Attachment B – Aerial Exhibit
Attachment C – USGS Exhibit
Attachment D – LiDAR Exhibit
Attachment E – Soil Data and Exhibit
Attachment F – Hingham Zoning By-Law Excerpts
Attachment G – Wetland Letter and Resource Area Exhibits
Attachment H – FEMA Exhibit
Attachment I – Record Utility Plans
Attachment J – Site Photos

ATTACHMENT A:
DEVELOPMENT AREA EXHIBIT



Source: Office of Geographic and Environmental Information (MassGIS), Commonwealth of Massachusetts Executive Office of Environmental Affairs; USGS Color Ortho Imagery - 15cm (2021)



Development Area Exhibit

100 Beal Street
Hingham, MA
December 20, 2023

BOHLER //

ATTACHMENT B:

AERIAL EXHIBIT



AERIAL FIGURE

100 BEAL STREET
HINGHAM, MA

PREPARED BY


BOHLER //

SCALE: 1"=300' DATE: 11/10/2023

ATTACHMENT C:

USGS EXHIBIT

ATTACHMENT D: LIDAR EXHIBIT



LIDAR TOPOGRAPHY FIGURE

**100 BEAL STREET
HINGHAM, MA**


PREPARED BY

BOHLER //

SCALE: 1"=300' DATE: 11/10/2023

ATTACHMENT E:
SOIL DATA AND EXHIBIT

Hydrologic Soil Group—Plymouth County, Massachusetts



**Natural Resources
Conservation Service**

Web Soil Survey
National Cooperative Soil Survey

11/10/2023
Page 1 of 4

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

Soil Rating Polygons

- | | | | |
|---|----------------------------|---|----------------------------|
|  | A |  | C |
|  | A/D |  | C/D |
|  | B |  | D |
|  | B/D |  | Not rated or not available |
|  | C | | |
|  | C/D | | |
|  | D | | |
|  | Not rated or not available | | |

Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

Soil Rating Lines

- | | |
|---|----------------------------|
|  | A |
|  | A/D |
|  | B |
|  | B/D |
|  | C |
|  | C/D |
|  | D |
|  | Not rated or not available |

Soil Rating Points

- | | |
|---|-----|
|  | A |
|  | A/D |
|  | B |
|  | B/D |

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Plymouth County, Massachusetts

Survey Area Data: Version 16, Sep 10, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 22, 2022—Jun 5, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
7A	Rainberry coarse sand, 0 to 3 percent slopes, sanded surface	A/D	1.0	1.1%
52A	Freetown muck, 0 to 1 percent slopes	B/D	21.1	21.8%
53A	Freetown muck, ponded, 0 to 1 percent slopes	B/D	2.7	2.8%
110B	Canton-Chatfield-Rock outcrop complex, 0 to 8 percent slopes, very stony	B	3.3	3.4%
262C	Quonset sandy loam, 8 to 15 percent slopes	A	4.3	4.4%
262E	Quonset sandy loam, 15 to 35 percent slopes	A	1.9	1.9%
305E	Paxton fine sandy loam, 25 to 35 percent slopes	C	8.4	8.7%
340C	Broadbrook very fine sandy loam, 8 to 15 percent slopes	C	11.5	11.9%
341B	Broadbrook very fine sandy loam, 3 to 8 percent slopes, very stony	C	9.6	10.0%
420C	Canton fine sandy loam, 8 to 15 percent slopes	B	0.0	0.0%
656B	Udorthents - Urban land complex, 0 to 8 percent slopes	B	2.6	2.7%
659B	Udorthents, 0 to 8 percent slopes, gravelly	B	30.4	31.4%
Totals for Area of Interest			96.9	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

ATTACHMENT F:
HINGHAM ZONING BY-LAW
EXCERPTS

SECTION III.

Use Regulations

III-A. Schedule of Uses

1. No building, structure, or land shall be used for any purpose or in any manner other than as set forth in the Schedule of Uses, Section III-A of this By-Law. The symbols "P", "A", and "O" as therein used having the following application:

P - Use permitted

A1 - Use allowed under a Special Permit by the Board of Appeals as provided in Section I-H

A2 - Use allowed under a Special Permit by the Board of Appeals as provided in Section I-H and subject to Site Plan Review by the Planning Board as provided in Section I-I

O - Use prohibited

2. Permitted uses and uses allowed by the Board of Appeals shall be in conformity with all dimensional requirements, off-street parking requirements, and all other applicable requirements of this By-Law. Allowed uses for projects authorized by a Mixed-Use Special Permit under Section IV-G are set forth in Section IV-G.
3. In accordance with Massachusetts General Laws Chapter 94G, Section 3(a)(2), all types of marijuana establishments, as defined in Massachusetts General Laws Chapter 94G, Section 1 and as may otherwise be defined by Massachusetts law or regulation, including, without limitation, all marijuana cultivators, marijuana testing facilities, marijuana product manufacturers, marijuana retailers, on-site consumption of marijuana, and any other types of licensed marijuana-related businesses, as well as businesses dealing in marijuana accessories, and the conducting of any such activity for commercial purposes by whatever name used, shall be prohibited within the Town of Hingham. This prohibition shall not be construed to prohibit Registered Marijuana Dispensaries to the extent permitted under this Zoning By-Law.

III-B. Special Conditions to Schedule of Uses

Special conditions shall apply as shown in Section III-A to such uses as are designated therein as being subject to one or more of the following special conditions:

1. The minimum lot size on which such use will be permitted shall be 2 acres. All buildings not used for residence shall be placed a minimum of 40 feet from the front, side and rear lot lines.
2. No part of such use shall be located within 1,000 feet of any residence district.
3. All setback requirements of the district in which the use subject to this special condition is located shall prevail and, in addition, no filling pump or any structure may be located within 25 feet of a property line or public way. A minimum of 1,000 square feet of paved area shall be provided for each filling pump. No more than two driveways of 26 foot width each shall be permitted per street. Curbing shall be installed along each line except at driveways.
4. No dwelling unit shall be leased or rented for a period of less than 30 consecutive days.

5. For properties zoned Industrial Park or Office Park that are included in the South Hingham Development Overlay District, refer to Section III-E, South Hingham Development Overlay District, for additional information regarding uses and dimensional criteria.
6. Subject to issuance of a temporary permit by the Building Commissioner pursuant to published regulations establishing hours of operation, size of lot, number and location of parking spaces, lighting, access and signage.
7. For parcels zoned Business A included in the Downtown Hingham Overlay District, refer to Section III-G, Downtown Hingham Overlay District, for additional information regarding permitted and prohibited uses and Design Review. Leased parking for Commercial/Residential Buildings is permitted only in conjunction with a Special Permit A2 for a Commercial/Residential Building and subject to the requirements of Section III-G, 7.a.
8. The following uses shall be allowed as of right to the extent required by M.G.L. c.40A, §3 but shall be subject to Site Plan Review in accordance with Section I-I of this By-Law, provided that the requirements of Section I-I may only be applied to such uses in a manner consistent with the provisions of M.G.L. c.40A, §3.
 - a. The uses set forth in Section III-A, subsections 2.1, 2.3, 4.5, 4.6 and 4.7.
 - b. To the extent included within the uses listed in Section III-A, subsections 3.1 through 3.4, inclusive of the use of land or structures for religious purposes or for educational purposes on land owned or leased by the commonwealth or any of its agencies, subdivisions or bodies politic or by a religious sect or denomination, or by a nonprofit educational corporation, and the use of land or structures, or the expansion of existing structures, for the primary, accessory or incidental purpose of operating a child care facility, all as set forth in M.G.L. c.40A, §3. Site Plan Review of these uses shall be limited to reasonable regulations concerning the bulk and height of structures, and determining yard sizes, lot area, setbacks, open space, parking and building coverage requirements, or such other matters which may be subject to regulation under M.G.L. c.40A, §3 as the same may be amended from time to time.
9. Registered Marijuana Dispensaries shall be allowed by Special Permit A2, subject to Section V-H, only for properties zoned Industrial Park or Office Park which are located in the South Hingham Development Overlay District.

III-A SCHEDULE OF USES

DISTRICTS

LEGEND

R=Residence B=Business OP= Office Park WB=Waterfront Business WR=Waterfront Recreation
 I=Industrial IP=Industrial Park LIP=Limited Industrial Park BR=Business Recreation OO=Official and Open Space

READ DOWN USING HEADINGS AT THE TOP OF THE PAGE

Residence					Business		Office Park*	Waterfront Business	Waterfront Recreation	Industrial	Industrial Park*	Limited Industrial Park	Business Recreation	Official and Open Space
A	B	C	D	E	A**	B								
1. RESIDENTIAL, subject to Special Condition 4 of Section III-B														
1.1 Single-Family Dwelling, together with such accessory buildings and structures as are customarily incidental thereto.														
P	P	P	O	P	O	O	O	O	O	O	O	O	O	O
1.2 Alteration and conversion of a Single-Family Dwelling containing at least 6 rooms exclusive of hall and bathroom existing prior to March 10, 1941, to accommodate not more than two families, provided that the exterior design of the structure is not changed from the character of a Single-Family Dwelling.														
A1	A1	A1	A1	A1	A1	A1	O	O	O	O	O	O	O	O
1.3 House trailer or mobile home, if approved by the Board of Health. The required authorization by the Board of Appeals may be granted for a period of not more than six months and shall be subject to renewal for only one additional six-month period.														
A1	A1	A1	A1	O	O	O	O	O	O	O	O	O	O	O
1.4 Apartment House, subject to the provisions of IV-E, Multi-Unit Development.														
O	O	O	O	O	A2	A2	O	O	O	O	O	O	O	O
1.5 Buildings containing multiple dwelling units, and community and other buildings accessory thereto, constructed and operated pursuant to the provisions of Section 38, 39, 40, and 41 of Chapter 121B of the Massachusetts General Laws, providing housing for elderly persons of low income, or constructed and operated pursuant to the provisions of Sections 25-32 of Chapter 121B of the Massachusetts General Laws, providing housing for persons of low and moderate income, subject to the provisions of IV-E, Multi-Unit Development. This use shall be exempt from subsection 4 of Section IV-C.														
A2	O	O	A2	A2	A2	A2	O	O	O	O	O	O	O	O
1.6 Town House – Not less than four nor more than ten connected dwelling units, subject to the provisions of IV-E, Multi-Unit Development.														
O	O	O	A2	A2	O	O	O	O	O	O	O	O	O	O

SECTION IV.

Intensity Regulations

IV-A. Schedule of Dimensional Requirements

No lot shall be created or subdivided and no building or structure shall be built, enlarged or located in such manner as does not conform to the requirements set forth in Sections IV-A, IV-B and IV-C of this By-Law.

minimum lot size		maximum height		maximum percentage which may be covered by all buildings	minimum yard dimensions			special requirements applicable to each district
area	frontage	feet	stories		front	side	rear	
RESIDENCE DISTRICT A								
20,000 sq. ft.	125'	35'	2½		25'	15'	15'	6, 9, 10, 13, 16
RESIDENCE DISTRICT B								
30,000 sq. ft.	150'	35'	2½		35'	20'	20'	6, 9, 13, 16
RESIDENCE DISTRICT C								
40,000 sq. ft.	150'	35'	2½		50'	20'	20'	6, 9, 13, 16
FLEXIBLE RESIDENTIAL DEVELOPMENT IN RESIDENCE DISTRICTS A THROUGH C								
All dimensional requirements for projects in Residence Districts A through C authorized by a Flexible Residential Development Special Permit under Section IV-D are set forth in Section IV-D.								
TOWN HOUSE IN RESIDENCE DISTRICT D								
5,000* sq. ft.	30' per dwelling unit	35'	2½	20%	50'	20'	20'	6, 9, 10, 11, 12, 16
*Per dwelling unit of one bedroom. For each additional bedroom, an additional 1,000 square feet of lot area is required.								
RESIDENCE DISTRICT E								
30,000 sq. ft.	150'	35'	2½		35'	20'	20'	6, 9, 10, 16

minimum lot size		maximum height		maximum percentage which may be covered by all buildings	minimum yard dimensions			special requirements applicable to each district
area	frontage	feet	stories		front	side	rear	
RETAIL GROUP IN INDUSTRIAL DISTRICT								
5 acres	300'	30'		30% / floor area ratio 0.60	40'	30'	30'	1, 2, 3, 4, 6, 7, 8
INDUSTRIAL PARK DISTRICT								
2 acres	250'	40'		40% / floor area ratio 0.35 permitted; 0.45 allowed by Special Permit A2	35'	35'	50'	1, 2, 3, 6, 14
RETAIL GROUP IN INDUSTRIAL PARK DISTRICT								
15 acres	500'	30'		20%	50'	50'	50'	1, 3, 4, 5, 6, 7, 8, 14
OFFICE PARK DISTRICT								
5 acres	200'	35'		Floor area Ratio of 0.15	100'	50'	50'	5, 6, 14
LIMITED INDUSTRIAL PARK DISTRICT								
2 acres	250'		30' not to exceed 2 stories	30% / floor area ratio of 0.35	35'	35'	50'	1, 2, 3, 6
OFFICIAL AND OPEN SPACE DISTRICT								
	20'	35'		10%	40'	40'	40'	1, 2, 5, 6, 15

IV-B. Special Requirements to Schedule of Dimensional Requirements

1. No building, structure, parking area or septic system shall be constructed within 100' of a residence district, except where the zoning district boundary is in a street, in which case the setback from said boundary shall be 50'. A natural or landscaped vegetative barrier as approved under Site Plan Review shall be retained or created and maintained within this setback.
2. A minimum of 15% of the area of each lot shall not be built upon, paved or parked upon, and shall be maintained either in its natural state or landscaped. Along the entire street frontage of each lot a green or landscaped strip not less than 15' wide shall be maintained in its natural state or landscaped with grass, trees and shrubs, not paved except for driveways, not parked upon and not built upon except for signs. The required 15% may include the 15' green strip.
3. Any yard space or area required to be kept open and unbuilt upon may, nevertheless, if otherwise lawful, be used for off-street automobile parking, or for outdoor storage of packaged articles, packaged supplies or packaged materials, provided any such outdoor storage space shall be effectively screened from view by some substantial means such as an ornamental wall an ornamental lattice or a dense planting. A green strip not less than thirty (30) feet wide on which to grow grass, bushes, flowers or trees, shall be maintained open and green, unbuilt upon, unused and unpaved and not parked upon, all along each side or rear property line of such a lot wherever it abuts land residentially zoned.
4. Frontage specified shall be the minimum width to a depth of 200'.
5. A green yard space not less than twenty (20) feet wide shall be maintained open and green with grass, bushes, flowers or trees or any combination of them, along the entire length of each side lot line or rear lot line of such a lot and (except for entrance and exit driveways) along the entire street frontage of such lot, and such yard space shall not be built on nor paved nor used for automobile parking. Not less than 80% of the land area of such a lot shall remain open and unbuilt on, but such open space may be used for automobile off-street parking, driveways, sidewalks and store service yards, except that such use shall not be permitted in any part of the 20' wide green perimeter strip above specified. Notwithstanding the foregoing, a green yard space not less than fifty (50) feet wide shall be maintained open and green with grass, bushes, flowers, trees, or in an undisturbed natural condition, or any combination of the foregoing, along the entire length of each side lot line and rear lot line of such lot where such side lot line or rear lot line abuts a Residence A or Residence B or Residence C District.
6. Site Plan Review to the extent required pursuant to Section I-I.
7. Each free standing structure, regardless of use, shall be not less than 1500 sq. feet lot coverage gross horizontal dimension. Each structure may be divided into street floor retail occupancy units not smaller than 750 sq. feet each, or into business, professional or personal service occupancy units not smaller than 350 sq. feet each.
8. No more than two driveways of 26' width each shall be permitted on the total street frontage of each retail store group.
9. In all residence districts and Business District A, the front setback may be as near the street as the average of the buildings or structures in the adjoining lots. For a vacant lot, the front setback line shall be the minimum front setback required in the district.

10. In the case of land used for housing the elderly persons of low income, or persons of low and moderate income, pursuant to the provisions of Section III-A, 1.5, the following provisions shall apply:
- a. There shall be no less than three thousand (3,000) square feet of lot area per dwelling unit.
 - b. No more than forty percent (40%) of the lot area shall be occupied by the buildings.
 - c. A green yard space, no less than twenty (20) feet wide, shall be maintained open and green with grass, bushes, flowers, or trees, or any combination thereof, along the entire length of each side lot line and rear lot line and (except for driveways) along the entire street frontage, and such green yard space shall not be built upon nor paved nor used for storage or for vehicle parking, but signs and fences not otherwise prohibited by law may be erected and maintained thereon.
 - d. There shall be a minimum distance of thirty (30) feet between all buildings on such land.
 - e. There shall be reserved sufficient areas to provide parking spaces for vehicles at the rate of one such space per dwelling unit. So much of said area or areas shall be paved as may be deemed necessary by the Board of Appeals. In making such determination, the Board of Appeals shall give due consideration to the location of the land, the probable number of vehicles parking thereon, the probable age, economic resources, and parking requirements of the occupants of such dwelling units, and such other factors as said Board may deem pertinent in each case. From time to time the Board of Appeals may, upon the petition of the Select Board, the Building Commissioner or the Planning Board, and after notice and hearing as provided by subsection 3 of Section I-D, determine the necessity for additional paving of such reserved area or areas and may order additional paving in accordance with such determination.
11. No side yard is required where a dwelling unit shares a party wall with a building constructed at the same time.
12. Not over 20% of the required minimum lot area may be met by land in the Floodplain Protection Overlay District.
13. No portion of the minimum lot area may be met by land that is:
- a. Wetlands as defined by Massachusetts General Laws Chapter 131, Section 40, the Wetlands Protection Act;
 - b. Wetlands as defined by the Town of Hingham's Wetlands Protection By-Law;
 - c. Land subject to flooding as defined by Massachusetts General Laws Chapter 131, Section 40, the Wetlands Protection Act; or
 - d. Land within the Floodplain Protection Overlay District as defined by Section III-C of the Zoning By-Law of the Town of Hingham.

In addition, the required minimum lot area shall be contiguous.

14. Properties zoned Industrial Park or Office Park and contained within the South Hingham Development Overlay District are subject to the intensity regulations set forth in Section III-E, South Hingham Development Overlay District.

15. Contiguous parcels separately deeded to the Town shall be considered a single parcel in application of minimum yard dimensions.

16. In no event shall the Height of any residential Building be higher than thirty-five (35) feet measured from Grade Plane, and in no event shall the highest roof surface, peak or parapet be more than forty (40) feet above Finished Grade where it intersects the perimeter wall at any point. See also the Building Height Diagram in Annex "A".


IV-C. General Intensity Provisions

1. Frontage

Lot frontage in all districts shall be measured at the street line, except that frontage shall be measured at the front setback line if the street is an arc of a curve with a radius of two hundred (200) feet or less. For this purpose, the setback line shall be the minimum front setback required in that district.


2. Lot Shape

- a. In addition to the required frontage and area, each lot shall be laid out so that a square with each side equal to eighty (80) percent of the required frontage for the zoning district in which it is located can be placed within the lot lines with at least one point on the front lot line.



- b. In addition, at no point between the front lot line or primary front lot line and the front wall of the principal structure shall the lot have a width of less than eighty (80) percent of the required frontage. Lot width is the horizontal distance between side lot lines, measured parallel to the lot frontage.

Hingham Massachusetts Zoning Parts A and C



0 0.5 1 2 3 4 Miles


Data from the Office of Geographic Information (MassGIS), Commonwealth of Massachusetts, MassIT and the Town of Hingham.
April 2019



The Town of Hingham makes no warranty or guarantee of the accuracy of the maps nor assumes responsibility for any errors or inaccuracies in these maps. The Town also takes no responsibility for any decision(s) made or action(s) taken as a result of reliance on these maps. The use of these maps is at the users' own risk.

Hingham Massachusetts

Zoning Part B Floodplain Protection Overlay District



0 0.5 1 2 3 4 Miles

Data from the Office of Geographic Information (MassGIS), Commonwealth of Massachusetts, MassIT and the Town of Hingham.
 May 2021



The Town of Hingham makes no warranty or guarantee of the accuracy of the maps nor assumes responsibility for any errors or inaccuracies in these maps. The Town also takes no responsibility for any decision(s) made or action(s) taken as a result of reliance on these maps. The use of these maps is at the users' own risk. Flood zone designations are based on 2012 and 2021 Flood Insurance Rate Maps issued by FEMA and revised by Letters of Map Revision effective August 14, 2015, September 8, 2017, and December 13, 2017 for the administration of the National Flood Insurance Program.

minimum lot size		maximum height		maximum percentage which may be covered by all buildings	minimum yard dimensions			special requirements applicable to each district
area	frontage	feet	stories		front	side	rear	
BUSINESS DISTRICT A								
	20'		3		10'			6, 9, 10
BUSINESS DISTRICT B								
	100'		3	25%	40'	25'	25'	2, 3, 6, 10
BUSINESS RECREATION DISTRICT								
10,000 sq. ft.	150'		2½	25%	40'	25'	25'	6, 2
WATERFRONT BUSINESS DISTRICT *								
10,000 sq. ft.	100'	20'		25%	40'	25'	10'	6
*For Waterfront Business District, yard dimensions are measured as follows:	Front: Side: Rear:	40 feet – measured horizontally at right angles to the sideline of the public way. 25 feet – of which a yard space not less than 5 feet wide shall be maintained opened and not parked upon, including parking overhang, along the entire length of each side lot line. Where adjacent property is below the mean high water line, the rear yard limitation shall apply, even if the adjacent property is subsequently filled to raise it above the mean high waterline. 10 feet measured horizontally from the shoreline which shall be maintained open and not parked upon along the entire length of the rear lot line.						
WATERFRONT RECREATION DISTRICT								
3 acres	150'	35'	3	20%	40'	25'	40'	5, 6
INDUSTRIAL DISTRICT								
80,000 sq. ft.	200'		3	40% / floor area ratio of 0.35 permitted; 0.50 allowed by Special Permit A2	40'	25'	25'	1, 3, 6
MIXED-USE PROJECT IN INDUSTRIAL DISTRICT								
All dimensional requirements for projects in the Industrial District authorized by a Mixed-Use Special Permit under Section IV-G are set forth in Section IV-G.								

ATTACHMENT G:
WETLAND LETTER AND
RESOURCE AREA EXHIBITS



500A Washington Street, Quincy, MA 02169

December 7, 2023

Bohler Engineering, Inc.
Attn: Angela Botto
45 Franklin Street, 5th Floor
Boston, MA 02110

Re: Wetland Summary Letter
100 Beal Street
Hingham, MA 02043

Dear Ms. Botto,

Professional Wetland Scientists (PWS) from Lucas Environmental, LLC (LE) conducted a site investigation on November 2, 2023 to determine if wetland resources were present at the property located at 100 Beal Street in Hingham, Massachusetts. Please note that this effort is specific to wetland resources; it does not evaluate constraints related to local planning or zoning requirements, historical or cultural significance, nor does it evaluate the potential for soil, air, or water contamination.

The wetland investigation was performed in accordance with the Massachusetts Wetlands Protection Act (M.G.L. Ch. 131, § 40) and regulations (310 CMR 10.00 *et seq.*); Section 404 of the Clean Water Act (33 U.S.C. 1344); Massachusetts Department of Environmental Protection (MassDEP) publication “Massachusetts Handbook for Delineation of Bordering Vegetated Wetlands (2022); and the U.S. Army Corp of Engineers (USACE) Wetland Delineation Manual (1987); the Northcentral and Northeast Regional Supplement (2012); and the Town of Hingham Wetlands Protection Bylaw (Article 22) and Wetland Regulations.

The site investigation was limited to wetland areas within 100 feet and perennial streams within 200 feet of the site property (the “Study Area”).

The following data sources were examined prior to the site investigation:

- Federal Emergency Management Agency (FEMA) Flood Insurance Rate Maps;
- United States Geological Survey (USGS) Topographic Quadrangle;
- USGS National Map Hydrography Datalayer;
- MassGIS MassDEP Wetland and Hydrography Datalayers;
- MassGIS Natural Heritage Atlas Datalayers; and
- United States Department of Agriculture, Natural Resources Conservation Service (USDA-NRCS) Soil Survey.

1.0 EXISTING CONDITIONS

The property, located at 100 Beal Street, includes an apartment building and associated parking area and driveways located at the northwest end of the property, with the remainder of the approximately 15-acre parcel consisting of forested uplands and wetlands. The property is bound by Beal Street and residential development to the north, residential development to the northwest, the Hingham Municipal Lighting Plant to the east, and undeveloped land of Bare Cove Park to the south and southwest. An unnamed perennial stream is mapped on the current USGS Topographic Map (Weymouth Quadrangle, 2021) along the southwest property line and then flows north and west to Beal Cove.

A review of the current MassGIS data layer for the Massachusetts Natural Heritage Atlas (effective August 1, 2021) under the Natural Heritage and Endangered Species Program (NHESP) indicates that the Study Area is not located within Priority Habitat of Rare Species or within Estimated Habitat of Rare Wildlife. A Certified Vernal Pool (CVP #3588) is mapped near the extreme southeast corner of the property.

Portions of the southern and eastern areas of the property are located within the Weymouth Back River Area of Critical Environmental Concern (ACEC), and the streams and wetlands within and draining to the ACEC are mapped as Outstanding Resource Waters (ORW). No MassDEP Wellhead Protection Areas or Watershed Protection Areas are mapped within the Study Area.

According to the July 17, 2012, FEMA Flood Insurance Rate Map (FIRM) for Plymouth County, Massachusetts, Map Number 25023C0081J, the entire Study Area is located in Zone X, Area of Minimal Flood Hazard, which is classified as areas outside the 0.2% annual chance floodplain (500-year floodplain). Therefore, Bordering Land Subject to Flooding (BLSF) is presumed not to be present within the Study Area.

2.0 ENVIRONMENTAL RESOURCE AREAS

Wetland resource areas observed within and near the Study Area include Inland Bank, Bordering Vegetated Wetlands (BVW), Land Under Water Bodies and Waterways (LUWW), and Riverfront Area (RFA). Three (3) Isolated Vegetated Wetlands (IVW) are also present within the Study Area. IVWs are not regulated under the WPA unless the wetland meets the size and volume requirement to be regulated as Isolated Land Subject to Flooding (ILSF). Although calculations were not performed, it does not appear that the IVW's within the Study Area meet the criteria to be regulated as ILSF under the WPA; however, the volume requirement under the Bylaw (one-sixteenth acre-foot) is less than under the WPA (one-quarter acre-foot). IVWs are regulated under the Bylaw. Under the Wetlands Protection Act (WPA) and Bylaw, the 100-Foot Buffer Zone associated with Bank and BVW extends into portions of the Study Area. The 200-Foot Riverfront Area associated with the unnamed perennial stream also extends into the Study Area.

A sub-meter survey of the delineation was completed on November 4, 2023 using a hand held Trimble GPS unit. An ESRI shapefile of wetland boundary locations compatible with ESRI ArcGIS 9.0+, NAD 83 Massachusetts State Plane, US feet, was prepared and provided to Bohler Engineering. The attached Figure 1 – Wetland Delineation Map identifies the location of the delineated resource areas.

2.1 Inland Bank – WPA & Bylaw

Section 310 CMR 10.54 of the WPA defines a Bank as *the portion of the land surface which normally abuts and confines a water body. It occurs between a water body and a vegetated bordering wetland and adjacent flood plain, or, in the absence of these, it occurs between a water body and an upland. The upper boundary of a Bank is the first observable break in the slope or the mean annual flood level, whichever is lower. The lower boundary of a Bank is the mean annual low flow level.* The delineated Bank of the perennial stream is described below. The Bylaw does not include any further definition of Bank.

2.2 Bordering Vegetated Wetlands – WPA & Bylaw

Section 310 CMR 10.55 of the WPA defines BVW as *“freshwater wetlands which border on creeks, rivers, streams, ponds and lakes. The types of freshwater wetlands are wet meadows, marshes, swamps and bogs. Bordering Vegetated Wetlands are areas where the soils are saturated and/or inundated such that they support a predominance of wetland indicator plants. The boundary of Bordering Vegetated Wetlands is the line within which 50% or more of the vegetational community consists of wetland indicator plants and saturated or inundated conditions exist...”* The delineated areas of BVW are described below. The Bylaw definition of Vegetated Wetlands is similar; however, it also includes IVW.

2.3 Land Under Water Bodies and Waterways – WPA & Bylaw

Section 310 CMR 10.56 of the WPA defines LUWW as *the land beneath any creek, river, stream, pond or lake. Said land may be composed of organic muck or peat, fine sediments, rocks or bedrock. The physical characteristics and location of Land Under Water Bodies and Waterways specified in 310 CMR 10.56(2)(a) are critical to the protection of the interests specified in 310 CMR 10.56(1). The boundary of Land Under Water Bodies and Waterways is the mean annual low water level.* This resource area is located below the lower edge of Bank or the Mean Annual High Water (MAHW) line of the perennial stream, therefore it is not field delineated. The Bylaw does not include any further definition of LUWW relative to rivers or streams.

2.4 Riverfront Area – WPA & Bylaw

Under Section 310 CMR 10.58 of the WPA, the Riverfront Area is *the area of land between a river's mean annual high-water line measured horizontally (outward from the river and a parallel line located 200 feet away). The riverfront area may include or overlap other resource areas or their buffer zones. The riverfront area does not have a buffer zone.* Furthermore, the MAHW line is *the line that is apparent from visible markings or changes in the character of soils or vegetation due to the prolonged presence of water and that distinguishes between predominantly aquatic and predominantly terrestrial land. Field indicators of bankfull conditions shall be used to determine the mean annual high-water line. Bankfull field indicators include but are not limited to: changes in slope, changes in vegetation, stain lines, top of pointbars, changes in bank materials, or bank undercuts.* The unnamed stream is depicted as perennial on the most recent USGS mapping (Weymouth, MA Quadrangle, 2021). Therefore the 200-Foot Riverfront Area extends landward from the MAHW line, which is coincident with the Inland Bank described below as Stream 1. The Bylaw definition of Riverfront Area is the same as the WPA.

However, Section 21.1(4) of the Regulations states: “Notwithstanding any provisions of 310 CMR 10.58, the Commission shall presume that the mean annual high water line of a non-tidal river is coincident with the outer (landmost) boundary of any Bordering Vegetated Wetland (as defined in these regulations) that may be adjacent to the river. This presumption may be overcome upon a clear showing that the mean annual high water line is closer to the river. Such evidence may include hydrological measurements and calculations prepared by a registered professional engineer and/or hydrologist, and/or stream flow stage data from U.S. Geological Survey stream gauges and survey. For non-tidal rivers lacking any Bordering Vegetated Wetland, the inner boundary of the 200-foot Riverfront Area shall be the top of Inland Bank as determined by the first observable break in slope or the mean annual flood level, whichever is lower.” The delineated MAHW line has been appropriately identified and delineated within the limits of the BVW.

2.5 Resource Area Descriptions

The following sections describe the delineated resources (BVW, Bank, and Bylaw regulated IVW) that were identified. BVW Determination Forms were completed and are included with this letter.

Stream 1 – Unnamed Perennial Stream

The unnamed perennial stream flows northwest generally along the western property line, then westerly away from the Study Area into Beal Cove. The Banks/MAHW line of the northern/eastern streambank was field delineated with blue survey flagging numbered sequentially from BF1-1 to BF1-38 and BF1-100 to BF1-123. Vegetation growing along the stream includes red maple (*Acer rubrum*), sweet pepperbush (*Clethra alnifolia*), northern arrowwood (*Viburnum recognitum*), silky dogwood (*Cornus amomum*), northern spicebush (*Lindera benzoin*), and skunk cabbage (*Symplocarpus foetidus*).

The MAHW line was delineated based on evidence of bankfull conditions and coincides with Inland Bank. The Bank along the stream is generally well defined, except between flags BF1-23 to BF1-38, where bank full conditions extend east into a large, flooded swamp. The stream varies in width from approximately eight to fifteen feet and observed depths were approximately six to ten inches. The stream bed consists largely of muck and fine sediments.

Wetland A – BVW

Wetland A is a red maple swamp Palustrine Forested Wetland (PFO) bordering on Stream 1. The wetland is delineated with pink survey tape numbered sequentially with flag series WFA-1 to WFA-100. Common vegetation within this wetland includes red maple, northern spicebush, glossy buckthorn (*Frangula alnus*), willows (*Salix sp.*), highbush blueberry (*Vaccinium corymbosum*), green ash (*Fraxinus pennsylvanica*), sweet pepperbush, northern arrowwood, common greenbrier (*Smilax rotundifolia*), meadowsweet (*Spiraea alba*), tussock sedge (*Carex stricta*), sensitive fern (*Onoclea sensibilis*), royal fern (*Osmunda regalis*), multiflora rose (*Rosa multiflora*), and skunk cabbage.

The wetland/upland boundary is generally located along a variable topographic break with several areas of broader transitional zones. Wetland soils consist of deep organic soil (histosol). Indicators of wetland hydrology include water-stained leaves, shallow soil saturation, free water in the soil test hole, and drainage patterns.

Common upland vegetation includes red oak (*Quercus rubra*), black cherry (*Prunus serotina*), white pine (*Pinus strobus*), Norway maple (*Acer platanoides*), white oak (*Quercus alba*), gray birch (*Betula alleghaniensis*), American hop-hornbeam (*Ostrya virginiana*), American beech (*Fagus grandifolia*), staghorn sumac (*Rhus typhina*), Oriental bittersweet (*Celastrus orbiculatus*), Tatarian honeysuckle (*Lonicera tatarica*), multiflora rose, American pokeweed (*Phytolacca americana*), garlic mustard (*Alliaria petiolata*), and tall goldenrod (*Solidago altissima*).

Wetland B – BVW

Wetland B is a PFO located in the west-central portion of the Study Area between Beal Street and Wetland A. The wetland is delineated with pink survey tape numbered sequentially with flag series WFB-1 to WFB-23. Common vegetation consists primarily of American elm (*Ulmus americana*), common buckthorn (*Rhamnus cathartica*), northern arrowwood, common greenbrier, and Tatarian honeysuckle.

Soils generally consist of a depleted matrix and redoximorphic features under a dark A horizon. Indicators of wetland hydrology include shallow soil saturation, inundation, and drainage patterns. Water flows through this wetland via culverts located at the north and south ends of the wetland and drains to Wetland A.

Wetland C – IVW

Wetland C is a small Palustrine Scrub-Shrub (PSS) wetland located just off-site along the northeast corner of the property. The wetland boundary was delineated with pink survey tape numbered sequentially with flag series WFC-1 to WFC-6. Plant species observed include primarily willow and glossy buckthorn. Soils have been excavated and are shallow with depletions.

Wetland D – IVW

Wetland D is a small PFO wetland located along the property line and Beal Street. The wetland boundary was delineated with pink survey tape numbered sequentially with flag series WFD-1 to WFD-6. Vegetation observed includes red maple, glossy buckthorn, northern arrowwood, common greenbrier, and poison ivy. Observed soil consists of a deep, dark A-horizon over a B-horizon with a depleted matrix. Hydrological indicators include water-stained leaves.

Wetland E – IVW

Wetland E is a very small PFO wetland located in the north-central portion of the Study Area. The wetland boundary was delineated with pink survey tape numbered sequentially with flag series WFE-1 to WFE-5. Observed vegetation includes one red maple tree, glossy buckthorn, common greenbrier, and hickory (*Carya sp.*). The soil consists of a deep, dark A-horizon over a B-horizon with a depleted matrix. No other indicators of wetland hydrology were observed. This area was previously delineated by others, and while it contains hydric soils, it is essentially devoid of vegetation and lacks hydrological indicators. It is arguably not a wetland resource area.



Wetland F – BVW

Wetland F is located off-site on the north side of Beal Street and consists of a drainage swale that drains to a culvert under Beal Street. The southern end of the wetland swale was delineated with pink survey tape numbered sequentially with flag series WFF-1 to WFF-4.

2.6 Hingham Wetlands Protection Bylaw

Under the Hingham Wetlands Protection Bylaw: *“The intent of the Conservation Commission is to move all structures and activities as far away as possible from any Resource Area, in order to protect the wetland values of Resource Areas. Except as otherwise specified, Resource Area buffers shall be retained and maintained in a naturally vegetated condition. Where buffer disturbance has occurred during construction, revegetation with native vegetation may be required. The Commission may require that already-altered buffer zone be restored in order to protect or improve Resource Area values. Restoration means planting native vegetation, grading, correcting site drainage, removing debris, or other measures which will improve, restore and protect the wetland values of the Resource Area.”*

The Bylaw Regulations define project-specific performance standards and setbacks for septic systems, pools and tennis courts, landscaping, docks and piers, underground storage tanks, filling, and structures. In addition to the project specific performance standards, the Conservation Commission may require a Conservation Restriction on land associated with new projects in any Resource Area, if the Commission deems it necessary to protect the wetland values of the Resource Area.


If you have any questions, please do not hesitate to contact me at 617.405.4140 or cml@lucasenviro.com. Thank you for your consideration in this matter.

Sincerely,
LUCAS ENVIRONMENTAL, LLC


A handwritten signature in blue ink that reads 'Christopher M. Lucas'.

Christopher M. Lucas, Manager, PWS/CWS/RPSS
Environmental Consultant/Wetland & Soil Scientist

Enclosures: Figure 1 – Wetland Delineation Map
BVW Determination Forms



Source: Office of Geographic and Environmental Information (MassGIS), Commonwealth of Massachusetts Executive Office of Environmental Affairs; USGS Color Ortho Imagery - 15cm (2021)



Wetland Delineation Map

Due Diligence
100 Beal Street
Hingham, MA

FIGURE 1



BORDERING VEGETATED WETLAND DETERMINATION FORM

Project/Site: 100 Beal Street City/Town: Hingham Sampling Date: 11/02/23
 Applicant/Owner: Town of Hingham Sampling Point or Zone: WFA-12 WET
 Investigator(s): Lucas Environmental, LLC Latitude / Longitude: _____
 Soil Map Unit Name: 52A - Freetown Muck NWI or DEP Classification: PFO

Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☒ No ☐ (If no, explain in Remarks)

Are Vegetation ☐, Soil ☐, or Hydrology ☐ significantly disturbed? (If yes, explain in Remarks)

Are Vegetation ☐, Soil ☐, or Hydrology ☐ naturally problematic? (If yes, explain in Remarks)

SUMMARY OF FINDINGS – Attach site map and photograph log showing sampling locations, transects, etc.

Wetland vegetation criterion met?	Yes ☒ No ☐	Is the Sampled Area within a Wetland?	Yes ☒ No ☐
Hydric Soils criterion met?	Yes ☒ No ☐		
Wetlands hydrology present?	Yes ☒ No ☐		
Remarks, Photo Details, Flagging, etc.:			

HYDROLOGY

Field Observations:		
Surface Water Present?	Yes ☐ No ☒	Depth (inches) _____
Water Table Present?	Yes ☒ No ☐	Depth (inches) <u>0.00</u>
Saturation Present (including capillary fringe)?	Yes ☒ No ☐	Depth (inches) <u>0.00</u>
Wetland Hydrology Indicators		
Reliable Indicators of Wetlands Hydrology	Indicators that can be Reliable with Proper Interpretation	Indicators of the Influence of Water
☒ Water-stained leaves ☐ Evidence of aquatic fauna ☐ Iron deposits ☐ Algal mats or crusts ☐ Oxidized rhizospheres/pore linings ☐ Thin muck surfaces ☐ Plants with air-filled tissue (aerenchyma) ☐ Plants with polymorphic leaves ☐ Plants with floating leaves ☐ Hydrogen sulfide odor	☐ Hydrological records ☒ Free water in a soil test hole ☒ Saturated soil ☐ Water marks ☐ Moss trim lines ☐ Presence of reduced iron ☐ Woody plants with adventitious roots ☐ Trees with shallow root systems ☐ Woody plants with enlarged lenticels	☐ Direct observation of inundation ☒ Drainage patterns ☐ Drift lines ☐ Scoured areas ☐ Sediment deposits ☐ Surface soil cracks ☐ Sparsely vegetated concave surface ☐ Microtopographic relief ☒ Geographic position (depression, toe of slope, fringing lowland)
Remarks (describe recorded data from stream gauge, monitoring well, aerial photos, previous inspections, if available):		

This form is only for BVW delineations. Other wetland resource areas may be present and should be delineated according to the applicable regulatory provisions.

VEGETATION – Use both common and scientific names of plants.

<u>Tree Stratum</u>		Plot size <u>30</u>		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name						
1. Red Maple	Acer rubrum	FAC	85.5	Yes	Yes		
2.							
3.							
4.							
5.							
6.							
7.							
8.							
9.							
				<u>85.5</u> = Total Cover			
<u>Shrub/Sapling Stratum</u>		Plot size <u>15</u>		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name						
1. Green Brier	Smilax rotundifolia	FAC	63.0	Yes	Yes		
2. Northern Arrowwood	Viburnum recognitum	FAC	38.0	Yes	Yes		
3. Glossy Buckthorn	Frangula alnus	FAC	20.5	No	Yes		
4.							
5.							
6.							
7.							
8.							
9.							
				<u>121.5</u> = Total Cover			
<u>Herb Stratum</u>		Plot size <u>5</u>		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name						
1. Skunk Cabbage	Symplocarpus foetidus	OBL	20.5	Yes	Yes		
2.							
3.							
4.							
5.							
6.							
7.							
8.							
9.							
10.							
11.							
12.							
				<u>20.5</u> = Total Cover			

VEGETATION – continued.

<u>Woody Vine Stratum</u>		Plot size _____		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name		Scientific name					
1.							
2.							
3.							
4.							
				0.0 = Total Cover			

Rapid Test: Do all dominant species have an indicator status of OBL or FACW? Yes ☐ No ☒				
Dominance Test:	Number of dominant species	Number of dominant species that are wetland indicator plants		Do wetland indicator plants make up $\geq 50\%$ of dominant plant species? Yes ☒ No ☐
	4	4		
Prevalence Index:		Total % Cover (all strata)	Multiply by:	Result
	OBL species		X 1	= 0.00
	FACW species		X 2	= 0.00
	FAC species		X 3	= 0.00
	FACU species		X 4	= 0.00
	UPL species		X 5	= 0.00
	Column Totals	(A) 0		(B) 0
Prevalence Index		B/A = 0.00		Is the Prevalence Index ≤ 3.0 ? Yes ☐ No ☐
Wetland vegetation criterion met? Yes ☒ No ☐				

Definitions of Vegetation Strata

- Tree - Woody plants 3 in. (7.62 cm) or more in diameter at breast height (DBH), regardless of height
- Shrub / Sapling - Woody plants less than 3 in. (7.62 cm) DBH and greater than or equal to 3.3 ft. (1 m) tall
- Herb - All herbaceous (non-woody plants, regardless of size, and woody plants less than 3.3 ft. (1 m) tall
- Woody vines - All woody vines greater than 3.3 ft. (1 m) in height

Cover Ranges	
Range	Midpoint
1-5 %	3.0 %
6-15 %	10.5 %
15-25 %	20.5 %
26-50 %	38.0 %
51-75 %	63.0 %
76-95 %	85.5 %
96-100 %	98.0 %

[illegible]²Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators (Check all that apply)		Indicators for Problematic Hydric Soils
☒ Histosol (A1)	☐ Polyvalue Below Surface (S8)	☐ 2 cm Muck (A10)
☐ Histic Epipedon (A2)	☐ Thin Dark Surface (S9)	☐ 5 cm Mucky Peat or Peat (S3)
☐ Black Histic (A3)	☐ Loamy Gleyed Matrix (F2)	☐ Iron-Manganese Masses (F12)
☐ Hydrogen Sulfide (A4)	☐ Depleted Matrix (F3)	☐ Mesic Spodic (A17)
☐ Stratified Layers (A5)	☐ Redox Dark Surface (F6)	☐ Red Parent Material (F21)
☐ Depleted Below Dark Surface (A11)	☐ Depleted Dark Surface (F7)	☐ Very Shallow Dark Surface (F22)
☐ Thick Dark Surface (A12)	☐ Redox Depressions (F8)	
☐ Sandy Mucky Mineral (S1)		
☐ Sandy Gleyed Matrix (S4)		
☐ Sandy Redox (S5)		☐ Other (Include Explanation in Remarks)
☐ Stripped Matrix (S6)		
☐ Dark Surface (S7)		

Restrictive Layer (if observed) Type: _____ Depth (inches): _____

Remarks: There is a shallow mineral fill layer over buried organic muck.

Hydric Soils criterion met? Yes ☒ No ☐

BORDERING VEGETATED WETLAND DETERMINATION FORM

Project/Site: 100 Beal Street City/Town: Hingham Sampling Date: 11/02/23
 Applicant/Owner: Town of Hingham Sampling Point or Zone: WFA-12 UPL
 Investigator(s): Lucas Environmental, LLC Latitude / Longitude: _____
 Soil Map Unit Name: 659B - Udorthents, gravelly NWI or DEP Classification: PFO

Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☒ No ☐ (If no, explain in Remarks)

Are Vegetation ☐, Soil ☐, or Hydrology ☐ significantly disturbed? (If yes, explain in Remarks)

Are Vegetation ☐, Soil ☐, or Hydrology ☐ naturally problematic? (If yes, explain in Remarks)

SUMMARY OF FINDINGS – Attach site map and photograph log showing sampling locations, transects, etc.

Wetland vegetation criterion met?	Yes ☐ No ☒	Is the Sampled Area within a Wetland?	Yes ☐ No ☒
Hydric Soils criterion met?	Yes ☐ No ☒		
Wetlands hydrology present?	Yes ☐ No ☒		
Remarks, Photo Details, Flagging, etc.:			

HYDROLOGY

Field Observations:		
Surface Water Present?	Yes ☐ No ☒	Depth (inches) _____
Water Table Present?	Yes ☐ No ☒	Depth (inches) _____
Saturation Present (including capillary fringe)?	Yes ☐ No ☒	Depth (inches) _____
Wetland Hydrology Indicators		
Reliable Indicators of Wetlands Hydrology	Indicators that can be Reliable with Proper Interpretation	Indicators of the Influence of Water
☐ Water-stained leaves ☐ Evidence of aquatic fauna ☐ Iron deposits ☐ Algal mats or crusts ☐ Oxidized rhizospheres/pore linings ☐ Thin muck surfaces ☐ Plants with air-filled tissue (aerenchyma) ☐ Plants with polymorphic leaves ☐ Plants with floating leaves ☐ Hydrogen sulfide odor	☐ Hydrological records ☐ Free water in a soil test hole ☐ Saturated soil ☐ Water marks ☐ Moss trim lines ☐ Presence of reduced iron ☐ Woody plants with adventitious roots ☐ Trees with shallow root systems ☐ Woody plants with enlarged lenticels	☐ Direct observation of inundation ☐ Drainage patterns ☐ Drift lines ☐ Scoured areas ☐ Sediment deposits ☐ Surface soil cracks ☐ Sparsely vegetated concave surface ☐ Microtopographic relief ☐ Geographic position (depression, toe of slope, fringing lowland)
Remarks (describe recorded data from stream gauge, monitoring well, aerial photos, previous inspections, if available):		

This form is only for BVW delineations. Other wetland resource areas may be present and should be delineated according to the applicable regulatory provisions.

VEGETATION – Use both common and scientific names of plants.

<u>Tree Stratum</u>		Plot size <u>30</u>		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name						
1. Norway Maple	Acer platanoides	FACU	85.5	Yes	No		
2. Black Cherry	Prunus serotina	FACU	20.5	No	No		
3. Black Oak	Quercus velutina	UPL	20.5	No	No		
4.							
5.							
6.							
7.							
8.							
9.							
				<u>126.5</u> = Total Cover			
<u>Shrub/Sapling Stratum</u>		Plot size <u>15</u>		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name						
1. Tatarian Honeysuckle	Lonicera tatarica	FACU	20.5	Yes	No		
2. European Privet	Ligustrum vulgare	FACU	10.5	Yes	No		
3. Shagbark Hickory	Carya glabra	FACU	10.5	Yes	No		
4.							
5.							
6.							
7.							
8.							
9.							
				<u>41.5</u> = Total Cover			
<u>Herb Stratum</u>		Plot size <u>5</u>		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name	Scientific name						
1. Garlic Mustard	Allaria petiolaris	FACU	20.5	Yes	No		
2. Tatarian Honeysuckle	Lonicera tatarica	FACU	20.5	Yes	No		
3.							
4.							
5.							
6.							
7.							
8.							
9.							
10.							
11.							
12.							
				<u>41.0</u> = Total Cover			

VEGETATION – continued.

<u>Woody Vine Stratum</u>		Plot size _____		Indicator Status	Absolute % Cover	Dominant? (yes/no)	Wetland Indicator? (yes/no)
Common name		Scientific name					
1.							
2.							
3.							
4.							
				0.0 = Total Cover			

Rapid Test: Do all dominant species have an indicator status of OBL or FACW? Yes ☐ No ☒				
Dominance Test:	Number of dominant species	Number of dominant species that are wetland indicator plants		Do wetland indicator plants make up $\geq 50\%$ of dominant plant species? Yes ☐ No ☒
	6	0		
Prevalence Index:		Total % Cover (all strata)	Multiply by:	Result
	OBL species		X 1	= 0.00
	FACW species		X 2	= 0.00
	FAC species		X 3	= 0.00
	FACU species		X 4	= 0.00
	UPL species		X 5	= 0.00
	Column Totals	(A) 0		(B) 0
Prevalence Index		B/A = 0.00		Is the Prevalence Index ≤ 3.0 ? Yes ☐ No ☐
Wetland vegetation criterion met? Yes ☐ No ☒				

Definitions of Vegetation Strata

- Tree - Woody plants 3 in. (7.62 cm) or more in diameter at breast height (DBH), regardless of height
- Shrub / Sapling - Woody plants less than 3 in. (7.62 cm) DBH and greater than or equal to 3.3 ft. (1 m) tall
- Herb - All herbaceous (non-woody plants, regardless of size, and woody plants less than 3.3 ft. (1 m) tall
- Woody vines - All woody vines greater than 3.3 ft. (1 m) in height

Cover Ranges	
Range	Midpoint
1-5 %	3.0 %
6-15 %	10.5 %
15-25 %	20.5 %
26-50 %	38.0 %
51-75 %	63.0 %
76-95 %	85.5 %
96-100 %	98.0 %

[illegible]


¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains ²Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators (Check all that apply)		Indicators for Problematic Hydric Soils
☐ Histosol (A1)	☐ Polyvalue Below Surface (S8)	☐ 2 cm Muck (A10)
☐ Histic Epipedon (A2)	☐ Thin Dark Surface (S9)	☐ 5 cm Mucky Peat or Peat (S3)
☐ Black Histic (A3)	☐ Loamy Gleyed Matrix (F2)	☐ Iron-Manganese Masses (F12)
☐ Hydrogen Sulfide (A4)	☐ Depleted Matrix (F3)	☐ Mesic Spodic (A17)
☐ Stratified Layers (A5)	☐ Redox Dark Surface (F6)	☐ Red Parent Material (F21)
☐ Depleted Below Dark Surface (A11)	☐ Depleted Dark Surface (F7)	☐ Very Shallow Dark Surface (F22)
☐ Thick Dark Surface (A12)	☐ Redox Depressions (F8)	
☐ Sandy Mucky Mineral (S1)		
☐ Sandy Gleyed Matrix (S4)		
☐ Sandy Redox (S5)		☐ Other (Include Explanation in Remarks)
☐ Stripped Matrix (S6)		
☐ Dark Surface (S7)		

Restrictive Layer (if observed)	Type: rock	Depth (inches): 18.00
--	------------	-----------------------

Remarks:

Hydric Soils criterion met? Yes ☐ No ☒



LEGEND



AREAS OF CRITICAL
ENVIRONMENTAL
CONCERN (ACECs)



100' BUFFER FOR
VERNAL POOL

RESOURCE AREA FIGURE

100 BEAL STREET
HINGHAM, MA

PREPARED BY

BOHLER //

SCALE: 1"=300' DATE: 11/10/2023


ATTACHMENT H:

FEMA EXHIBIT

National Flood Hazard Layer FIRMette



70°55'2"W 42°14'41"N



1:6,000

70°54'25"W 42°14'14"N

Basemap Imagery Source: USGS National Map 2023

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance Water Surface Elevation
		17.5 Cross Sections with 1% Annual Chance Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
		Coastal Transect Baseline
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped





The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **11/10/2023 at 5:53 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

ATTACHMENT I:
RECORD UTILITY PLANS



LEGEND

EXISTING

DESCRIPTION

30	2' CONTOUR
+30.5	SPOT ELEVATION
	PROPERTY LINE
	CONCRETE PAD
	EDGE OF PAVEMENT
	VERTICAL GRANITE CURB
	SLOPE GRANITE CURB
	CAPE COD BERM
	EDGE OF GRAVEL
	RETAINING WALL
	STONE RETAINING WALL
	WATER LINE
	GAS LINE
	OVERHEAD WIRE
	SEWER LINE
	DRAIN LINE
	FENCE
	100' WETLAND BUFFER
	50' WETLAND BUFFER
	WETLAND LINE
	MARSH
	WELL
	HYDRANT
	WATER GATE
	GAS GATE
	GAS METER
	ELECTRICAL METER
	LIGHT
	UTILITY POLE
	SEWER MANHOLE
	UNIDENTIFIED MANHOLE
	TELEPHONE MANHOLE
	DRAIN MANHOLE
	CATCH BASIN
	DETECTABLE MAT
	SIGN
	BOULDER
	CONIFEROUS
	DECIDUOUS
	STONE POST GUARD RAIL

NOTES:

- PROPERTY LINE, STREET LINE AND OWNER INFORMATION WAS COMPILED FROM RECORDS ON FILE AT THE PLYMOUTH COUNTY REGISTRY OF DEEDS AND THE TOWN OF HINGHAM ASSESSORS DEPARTMENT.
- TOPOGRAPHY INFORMATION SHOWN ON THIS PLAN IS BASED UPON AN ON THE GROUND SURVEY PERFORMED BY MERRILL CORPORATION DURING THE MONTH OF DECEMBER OF 2015.
- ALL ELEVATIONS ARE BASED ON THE NATIONAL GEODETIC VERTICAL DATUM (NGVD) OF 1929.
- WETLAND RESOURCE AREAS SHOWN ON THIS PLAN WERE DELINEATED BY ENVIRONMENTAL CONSULTANTS AND RESTORATION, LLC DURING DECEMBER OF 2015 AND LOCATED BY MERRILL CORPORATION.
- SUBJECT SITE IS IN THE "OFFICIAL AND OPEN SPACE" ZONING DISTRICT AS DEPICTED ON THE TOWN OF HINGHAM ZONING MAP.
- EXISTING UTILITIES, WHERE SHOWN, HAVE BEEN COMPILED BASED ON OBSERVED ABOVE GROUND EVIDENCE AND AVAILABLE RECORD PLANS AND ARE TO BE CONSIDERED APPROXIMATE. MERRILL CORPORATION DOES NOT GUARANTEE THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN OR THAT ALL EXISTING UTILITIES AND/OR SUBSURFACE STRUCTURES ARE SHOWN.
- APPROVAL BY MASSACHUSETTS DEPARTMENT OF TRANSPORTATION MAY BE REQUIRED FOR THE REMOVAL OF THE RAILROAD TRACKS RUNNING IN FRONT OF THE SUBJECT PROPERTY. NO EASEMENT DOCUMENT ENCOUNTERED DURING THE SURVEY.


RECORD OWNER:

ASSESSORS MAP 69 LOT 50
2 BEAL STREET

TOWN OF HINGHAM
210 CENTRAL STREET
HINGHAM, MA 02043
DEED BOOK 3961 PAGE 701

FLOOD NOTE:

BY GRAPHIC PLOTTING ONLY, THIS PROPERTY IS LOCATED IN ZONE "X" OF THE FLOOD INSURANCE RATE MAP, AS SHOWN ON COMMUNITY PANEL No. 250268 0082J, WHICH BEARS AN EFFECTIVE DATE OF JULY 17, 2012, AND IS NOT IN A SPECIAL FLOOD HAZARD AREA.



REVISIONS



DRAWN BY: VC

DESIGNED BY:

CHECKED BY: SMB

Merrill
Engineers and Land Surveyors
427 COLUMBIA ROAD, HANOVER, MA 02339 / T: (781) 826-9200
26 UNION STREET, PLYMOUTH, MA 02360 / T: (508) 746-6060
WWW.MERRILLINC.COM

EXISTING CONDITIONS PLAN

SELECTMEN'S PARCEL - 2 BEAL STREET
HINGHAM, MASSACHUSETTS

HINGHAM AFFORDABLE HOUSING TRUST
PREPARED FOR: 210 CENTRAL STREET
HINGHAM, MA 02043

DECEMBER 22, 2015



SCALE: 1"=40'

JOB No. 15-253

LATEST REVISION:

EXISTING CONDITIONS
PLAN

SHEET 1 OF 2



ATTACHMENT J:

SITE PHOTOS